



Acting as the main contractor responsible for pile driving and rock socketing on this project in the Port of Halifax, Bermingham was instrumental in overcoming several obstacles including obstructions and Halifax's hard maritime rock. The project consisted of 30" diameter piles driven to bedrock using a down the hole hammer and rock socketed into bedrock using Bermingham's BHD-40 Drill which was attached to 140 ft of Bermingham's L27 VTL.

